

An Integrated Framework for Improving Construction Productivity in Saudi Industrial Projects¹

Linking Workforce Readiness, Advanced Work Packaging, Modularization, Lean Execution, Climate-Adaptive Planning, and Digitalization Governance

By Saad A. Al-Wahaib and Abdul Rahman Habib

Saudi Aramco, Riyadh, Kingdom of Saudi Arabia

Abstract

Construction productivity in Saudi industrial projects is affected by interdependent climatic, supply-chain, engineering, workforce, logistics, safety, subcontractor, and workforce-readiness constraints. These constraints are particularly important in oil and gas, petrochemical, refinery, gas processing, utilities, and chemical process industry projects, where construction delay can affect mechanical completion, commissioning, start-up, revenue realization, and wider industrial-development objectives.

Although prior studies and industry guidance have examined labor productivity factors, heat stress, lean construction, modularization, Advanced Work Packaging (AWP), and digital construction methods, these topics are often treated separately. Limited literature integrates these drivers into a field-oriented diagnostic and mitigation framework tailored to the Saudi and wider GCC industrial-project context, where extreme climate, imported supply chains, multinational workforces, EPC interface complexity, permit-to-work controls, and workforce-readiness failures frequently occur simultaneously.

This paper develops an integrated construction productivity framework using a structured literature-informed synthesis of academic and industry sources from 2015–2025, supplemented by established foundational productivity literature and professional practice insights from Saudi and GCC industrial project execution. The framework identifies major productivity loss mechanisms, links them to measurable field indicators, and maps them to practical mitigation strategies including AWP, modularization, lean execution, climate-adaptive planning, digital workforce-readiness systems, and KPI-based productivity governance. The contribution is a defensible practice-oriented framework for improving workforce readiness, reducing non-productive time, improving workflow reliability, and supporting productivity governance in Saudi

¹ How to cite this paper: Al-Wahaib, S. A., Habib, A. R. (2026). An Integrated Framework for Improving Construction Productivity in Saudi Industrial Projects; *PM World Journal*, Vol. XV, Issue VIII, August.

industrial projects. The paper is positioned as a structured framework synthesis rather than a primary statistical or project-dataset-based empirical study.

Keywords: Construction productivity; Saudi Arabia; industrial projects; Advanced Work Packaging; modularization; lean construction; workface readiness; Work Sampling; Five-Minute Rating; Craftsman Questionnaire Sampling; heat stress; Ramadan productivity; supply-chain resilience; EPC projects; project controls; BIM; digitalization framework; productivity governance.

1. Introduction

The Gulf Cooperation Council (GCC) region has experienced sustained investment in upstream oil and gas, gas processing, petrochemical integration, refinery modernization, LNG infrastructure, industrial utilities, hydrogen-related developments, and economic diversification programs. Within this regional context, the Kingdom of Saudi Arabia (KSA) is particularly significant because of the scale of its capital-project portfolio, its role in global energy and industrial markets, and the continuing transformation associated with Vision 2030. [7,27,28]

Industrial construction productivity is a strategic issue rather than merely a site-level performance concern. Delays in construction execution can affect mechanical completion, commissioning, plant start-up, revenue realization, downstream integration, supply-chain commitments, and national industrial development objectives. In Saudi industrial projects, productivity performance is shaped by a combination of extreme heat, humidity, dust exposure, long-lead imported equipment, multinational workforces, EPC interface complexity, engineering readiness, permit-to-work controls, and brownfield access restrictions. [8,9,27,28]

Existing literature provides valuable insights into labor productivity, lean construction, work sampling, heat stress, AWP, modularization, BIM, and construction digitalization. However, many studies examine these drivers separately. A practical gap remains in integrating these variables into a diagnostic framework for Saudi industrial megaprojects, where climatic exposure, supply-chain dependency, engineering readiness, material availability, permit constraints, subcontractor interfaces, and workforce diversity interact at the workface.

This paper addresses that gap by developing a structured, literature-informed productivity framework calibrated to Saudi industrial project execution realities. The study does not claim to test a statistical multivariate model using project-level productivity datasets. Rather, it synthesizes academic literature, established industry guidance, and professional practice insights into a practical diagnostic and mitigation framework that can be validated by future empirical studies.

The objectives of this study are: (1) to identify the major productivity-loss drivers affecting Saudi industrial construction projects; (2) to classify these drivers into climatic, supply-chain, engineering, workforce, logistical, safety, subcontractor, and workface-readiness dimensions; (3) to map each driver to measurable field indicators and appropriate diagnostic methods; and (4) to develop an integrated mitigation framework combining AWP, modularization, lean execution,

digital workforce-readiness systems, climate-adaptive planning, and KPI-based productivity governance.

The guiding research questions are: What are the dominant productivity loss mechanisms in Saudi industrial projects? How can work sampling, Five-Minute Rating, CQS, delay modelling, workforce-readiness metrics, and PPC be integrated into a practical diagnostic system? Which mitigation strategies are most appropriate for each category of productivity loss, and how can they be governed across the project lifecycle?

Figure 1 summarizes the overall framework used in this paper and shows the relationship between productivity challenges, enablers, execution governance, and project outcomes.

Integrated Construction Productivity Improvement Framework




Figure 1. Integrated Framework for Construction Productivity Improvement in Saudi Industrial Projects

2. Literature Review: Productivity Drivers, Concepts, and Research Gaps

2.0 Construction Productivity Concepts and Measurement Basis

For this paper, construction productivity is treated as a workforce-level system outcome rather than a simple measure of labor effort. Direct work refers to activities that physically advance installation or construction quantities. Support work includes necessary enabling activities such as tool preparation, material handling, access preparation, quality checks, and supervision. Non-productive time includes waiting, idle time, excessive walking, rework, access restrictions, permit delays, missing materials, missing information, and other conditions that consume labor hours

without advancing installation. This distinction is central to the framework because many apparent labor-efficiency problems are actually workplace-readiness failures.

The framework therefore emphasizes indicators that help distinguish labor efficiency problems from systemic readiness failures. These include installed quantity per man-hour, direct/support/non-productive work proportions, Percent Plan Complete (PPC), IWP constraint-free release, material kitting status, IFC drawing availability, TQ/RFI closure, permit readiness, rework man-hours, and schedule variance. This distinction is essential because adding manpower rarely improves productivity when workfronts remain incomplete or constraints remain unresolved.

Evidence hierarchy is treated explicitly in this review. Peer-reviewed construction productivity literature is used as the primary evidence base; CII, PMI, ISO, ILO, OSHA, World Bank, and selected industry reports are used as recognized professional guidance; and the authors' practice experience is used only to contextualize framework application for Saudi and GCC industrial projects, not as independently verified empirical proof.

2.1 Labor Competency, Training, and Workforce Dynamics

The human element remains one of the most influential variables in construction productivity. KSA industrial projects typically rely on large multinational workforces with varying skill levels, languages, training backgrounds, and supervision practices. This creates operational flexibility but also introduces communication challenges, productivity variability, rework potential, and safety exposure. [8,9]

Research indicates that labor skill, training quality, experience, and workforce stability are primary predictors of output quality. Studies using production-function approaches in KSA have suggested that productivity improvement depends not only on increasing labor input but also on effective use of capital equipment, construction technology, and skilled operation of advanced systems. In practical terms, additional manpower alone cannot solve productivity problems if the workforce lacks tools, drawings, permits, materials, access, or competent supervision.

Extended overtime is frequently used to recover schedule delays, but construction productivity research consistently shows that prolonged overtime generates diminishing returns through fatigue, absenteeism, safety risk, reduced concentration, and rework. [8] Sustainable productivity improvement requires balanced workforce planning, effective supervision, technical training, field-level communication, and disciplined short-interval control rather than excessive reliance on overtime.

2.2 Environmental Stressors: Heat, Humidity, Dust, and Wind

Extreme climate is one of the most visible and persistent productivity constraints in GCC industrial construction. During peak summer periods, ambient temperatures frequently exceed 45°C, while coastal regions such as KSA's Eastern Province and Red Sea areas may experience

high humidity that increases heat stress through reduced evaporative cooling. Heat stress reduces physical endurance, increases rest-cycle requirements, raises hydration needs, and can reduce effective working time. [27,28]

The productivity impact of heat is not only a welfare issue; it is a direct schedule and cost driver. Labor-intensive activities such as scaffolding, structural steel erection, piping installation, insulation, refractory work, cable pulling, and manual material handling become slower and more safety-sensitive during high heat-index periods. Wind and dust conditions may also restrict crane lifts, elevated work, exterior installation, and logistics movements, creating fragmented workflows and idle time.

Saudi industrial projects should therefore include heat-adaptive productivity factors in baseline planning. Work-rest cycles, night-shift optimization, shaded work areas, hydration stations, cooling shelters, wearable heat monitoring, and dynamic scheduling based on Wet Bulb Globe Temperature (WBGT) or heat-index data should be treated as formal productivity controls rather than temporary site accommodations. [27,28]

2.3 Ramadan and Cultural Calendar Effects

The holy month of Ramadan introduces a distinct and predictable productivity variable that is frequently under-addressed in formal project planning. During Ramadan, working hours in KSA are typically reduced by regulatory requirement, and workforce energy levels, hydration, and physical endurance are affected by fasting obligations. Night-shift patterns may be altered, and coordination across international teams becomes more complex.

Industry practice in KSA commonly applies Ramadan productivity allowances for labor-intensive activities, especially when Ramadan overlaps with peak heat exposure. Because peer-reviewed activity-level measurement of Ramadan productivity in Saudi industrial construction remains limited, any percentage allowance should be treated as a planning assumption to be calibrated using actual project records. Baseline schedules should nevertheless model Ramadan timing explicitly across the project duration, and high-intensity activities such as major concrete pours, module installations, or shutdown windows should be sequenced outside Ramadan periods where practicable. [27,28,47]

2.4 Supply-Chain Volatility and Material Logistics

KSA industrial projects depend heavily on local and international supply chains for process equipment, rotating machinery, specialized valves, structural steel, piping, electrical systems, instrumentation, control systems, fabricated modules, and vendor packages. Global logistics volatility, shipping delays, customs bottlenecks, port congestion, and vendor capacity limitations can directly affect field productivity. [29,30]

Material delay does not simply postpone one activity; it fragments workfronts, forces crews to move between areas inefficiently, increases out-of-sequence construction, and generates

additional supervision and coordination effort. Material readiness must therefore be integrated with AWP, workface planning, kitting, laydown management, and digital tracking. Procurement status alone is insufficient unless the correct materials are available in the right quantity, location, condition, and sequence at the right time.

2.5 Interface Management, Engineering Readiness, and Design Complexity

Industrial projects are characterized by dense technical interfaces between owners, licensors, engineering contractors, procurement teams, vendors, construction contractors, subcontractors, operations, quality, safety, and commissioning organizations. Late design changes, incomplete IFC drawings, unresolved technical queries, inconsistent material take-offs, and weak constructability reviews can substantially reduce field productivity. [9,10,26]

Brownfield industrial projects are particularly vulnerable because operational permits, SIMOPS controls, shutdown windows, tie-in restrictions, existing underground services, and limited access reduce execution flexibility. Productivity in such environments depends heavily on early constructability input, laser scanning, 3D model reviews, interface registers, shutdown planning, temporary works engineering, and disciplined work package readiness.

2.6 Safety, Permit-to-Work Systems, and SIMOPS

Safety management is a critical productivity variable often treated separately from construction execution planning. In practice, permit-to-work (PTW) systems, simultaneous operations (SIMOPS) controls, isolation procedures, H2S gas exposure protocols, and stop-work obligations directly affect when and how construction activities can proceed. PTW delays are a common source of non-productive waiting time that is systematically under-reported because it is classified as a safety requirement rather than a productivity loss.

Effective integration of safety planning with AWP and workface planning is therefore essential. IWPs should explicitly identify safety prerequisites — including PTW types, isolation requirements, exclusion zones, and inspection points — and these should be verified as part of the pre-mobilization constraint review. Proactive SIMOPS planning and advance coordination with operations teams can reduce the productivity impact of permit backlogs and access restrictions. [7,23,24]

2.7 Subcontractor Management and Multi-Tier Execution

KSA industrial projects are typically executed through multi-tier subcontracting structures, where main EPC contractors engage multiple subcontractors across civil, structural, piping, mechanical, electrical, instrumentation, insulation, painting, and scaffolding disciplines. Subcontractor performance variability, capability gaps, back-to-back contract terms that misalign incentives, and coordination challenges between parallel subcontracting packages are significant but often under-acknowledged productivity inhibitors.

Subcontractor productivity management requires the same tools and disciplines applied to the main contractor workforce: AWP-aligned IWP packages, Work Sampling and CQS diagnostics, short-interval control, and KPI monitoring. Main contractors should ensure that subcontractors have full access to work package content, constraint information, and planning tools, and that performance accountability is embedded in subcontract terms and day-to-day site management. [7,23,24]

The literature review indicates that the key research gap is not the absence of productivity tools, but the lack of integration among them for the Saudi industrial context. The proposed framework responds to this gap by connecting productivity drivers, field indicators, diagnostic techniques, mitigation strategies, and governance controls within one workplace-oriented system.

Table 1. Literature Synthesis Matrix: Major Productivity Drivers and Relevance to Saudi Industrial Projects

Productivity driver	Representative literature / source base	Typical method or evidence type	Productivity mechanism	Limitations / KSA relevance
Labor competency and supervision	Hanna et al.; Thomas & Horman; KSA labor productivity studies [8,9,42]	Empirical productivity studies; workforce management literature	Skill variation, overtime fatigue, supervision quality, communication effectiveness	Requires integration with multilingual workforce management and subcontractor structures common in KSA industrial projects.
Heat stress, humidity, dust, and seasonal exposure	OSHA; ILO; GCC/KSA climate and safety guidance [27,28]	Occupational health guidance; climate-productivity studies	Reduced effective working time, increased rest cycles, restricted high-risk work, safety exposure	Needs explicit WBGT or heat-index planning in schedule baselines and work-rest protocols.
Supply-chain and material readiness	World Bank, McKinsey, AWP/material management sources [29,30,4,5]	Industry reports; project controls and logistics guidance	Material shortages fragment workfronts and increase waiting, resequencing, and idle time	Highly relevant where imported equipment, customs clearance, vendor capacity, and laydown sequencing affect field work.
Engineering readiness and design change	Love et al.; project management and constructability sources [10,24,25,26]	Rework and project management literature	Late IFC drawings, TQs/RFIs, MTO errors, design changes, and interface gaps create stoppage and rework	Especially significant in EPC, brownfield, SIMOPS, and licensor-interface environments.

Productivity driver	Representative literature / source base	Typical method or evidence type	Productivity mechanism	Limitations / KSA relevance
AWP and workforce readiness	CII RT-272, RT-319, AWP body of knowledge [4-6]	Industry research and best-practice validation	Constraint-free IWPs align engineering, procurement, permits, materials, tools, access, and inspections before crew mobilization	Strong practical relevance; requires early implementation and management discipline to avoid becoming documentation-only.
Lean execution and workflow reliability	Ballard, Koskela, Last Planner System, lean construction studies [1-3,13-16]	Lean construction theory and case-based practice evidence	Pull planning, look-ahead planning, PPC, and short-interval control reduce variability and workflow interruptions	Needs cultural adaptation in hierarchical EPC and subcontractor environments.
Modularization and industrialized construction	Industrial modularization literature and oil/gas case studies [17-22]	Case studies, decision frameworks, comparative studies	Transfers field scope to controlled fabrication environments, reducing site labor, congestion, heat exposure, and rework	Requires early FEED decisions, route studies, heavy-lift planning, and dimensional control.
Digitalization and BIM	BIM, ISO 19650, digital construction sources [11,12,48-51]	Technology guidance; digital construction studies	Improves visibility of readiness, progress, clashes, material status, RFIs, and emerging delay risks	Benefits depend on integration with AWP, project controls, and field reporting rather than isolated technology deployment.

3. Methodology

3.1 Study Design

This paper adopts a structured narrative review and framework-development methodology. The purpose is not to estimate statistical coefficients or validate an integrated productivity model using project-level datasets. Instead, the study synthesizes academic literature, recognized industry guidance, and professional practice insights to develop an integrated diagnostic and mitigation framework for Saudi industrial construction projects. The method is deliberately positioned as a structured practice-oriented synthesis rather than a PRISMA-style systematic review or a primary empirical study.

3.2 Source Identification and Search Strategy

Academic and technical sources were identified through Scopus, Web of Science, ASCE Library, Engineering Village, ScienceDirect, Google Scholar, CII publications, PMI guidance, ILO and OSHA heat-stress guidance, ISO BIM standards, and selected industry reports. The primary review period was 2015–2025, with earlier foundational productivity and lean construction works retained where they remain widely cited and methodologically relevant. Search terms included combinations of: construction productivity, Saudi Arabia, GCC construction, industrial construction, labor productivity, work sampling, Five-Minute Rating, Craftsman Questionnaire Sampling, AWP, Advanced Work Packaging, workplace planning, IWP, modularization, lean construction, Last Planner System, heat stress, WBGT, supply-chain delay, BIM, digital construction, digitalization framework, and project controls.

3.3 Inclusion, Exclusion, and Evidence Classification

Sources were included where they addressed construction productivity mechanisms, field measurement methods, industrial project execution, GCC or Saudi construction conditions, AWP, modularization, lean workflow, digital workplace-readiness systems, climate effects, or project governance. Sources were excluded where they were only marginally related to construction productivity, lacked technical relevance to industrial execution, or provided generic management commentary without connection to measurable productivity mechanisms. Evidence was classified into three categories: peer-reviewed academic studies; recognized industry guidance and standards; and professional practice evidence used to contextualize the framework for Saudi/GCC industrial projects.

3.4 Coding and Framework Development

The literature and practice evidence were coded against recurring productivity-loss categories: climate and calendar effects, labor competency, engineering readiness, material readiness, logistics reliability, safety and permit-to-work controls, subcontractor interfaces, rework, crew congestion, AWP maturity, modularization potential, lean workflow reliability, and digitalization-governance capability. Each category was mapped to field indicators, likely productivity impacts, diagnostic tools, and mitigation strategies. This coding process produced the integrated driver framework presented in Section 5 and the mitigation framework presented in Section 6.

3.5 Use of Illustrative Application Scenarios

The scenarios in Section 7 are illustrative application scenarios derived from the authors' professional experience in Saudi and GCC industrial project environments and from published industry practice. They are not presented as independently audited empirical case studies and do not disclose confidential project data. Their purpose is to demonstrate how the framework can be applied to typical industrial construction situations involving AWP, modularization, lean

execution, skid-mounted systems, BIM-enabled coordination, and digital workforce-readiness systems.

3.6 Methodological Limitations

The principal limitation of the methodology is that it relies on literature synthesis and representative practice scenarios rather than a validated multi-project productivity dataset. Therefore, the framework should be interpreted as a structured diagnostic and mitigation model for practice and future validation, not as proof of causal effectiveness or as a statistical productivity model. Future work should test the framework using field observations, work sampling datasets, IWP readiness records, material availability logs, WBGT data, PPC records, installed quantities, man-hours, and project performance outcomes.

4. Productivity Measurement and Diagnostic Techniques

Effective productivity improvement requires objective diagnosis. Without reliable measurement, project teams may incorrectly attribute poor productivity to craft performance when the real causes are missing materials, poor access, unresolved drawings, weak supervision, late inspections, or excessive movement. Quantitative measurement tools provide the factual basis required for targeted corrective action. [21,23]

4.1 Field Rating and Comprehensive Site Reporting

Field rating involves systematic observation of construction crews to determine how much time is spent on direct productive work, support work, or non-productive activities. When combined with daily site reporting, it creates a baseline for identifying underperforming work areas, trades, or execution conditions. Field reports should capture not only progress quantities but also reasons for lost productivity, such as missing tools, late permits, poor access, crane unavailability, or material shortages.

4.2 Work Sampling

Work Sampling is a statistically based observational method used to estimate the proportion of time spent on different activity categories. Random observations are collected over time and classified into productive, contributory, and non-productive categories. Because it is less intrusive than continuous time study, Work Sampling is well suited for industrial sites where multiple crews and workfronts operate simultaneously. It can reveal hidden losses such as tool searching, excessive walking, waiting for materials, or idle time caused by poor coordination. [23,38]

4.3 Five-Minute Rating (FMR) Technique

The Five-Minute Rating technique provides a rapid field diagnostic method for short-cycle observations. A supervisor or observer reviews crew activity during a short interval and records

whether workers are productively engaged. Although less statistically rigorous than formal Work Sampling, it is useful for quick identification of productivity hotspots, bottlenecks, and immediate corrective actions. It is particularly valuable during shutdowns, maintenance tie-ins, or short-duration work campaigns where fast feedback is more important than statistical precision. [23,44]

4.4 Craftsman Questionnaire Sampling (CQS)

Craftsman Questionnaire Sampling combines quantitative observation with qualitative worker feedback to explain why productivity losses occur. For example, Work Sampling may reveal high idle time, but CQS may identify that the cause is late permits, missing drawings, unavailable scaffolding, unclear instructions, or waiting for inspection. This method is particularly valuable in Saudi projects where multinational workforces and layered subcontracting structures can obscure root causes from senior management. [45]

4.5 Delay Modeling and Root-Cause Analysis

Delay modeling uses historical project data, CPM schedules, and delay attribution methods to identify the primary drivers of schedule slippage. By linking productivity losses to weather, material delay, design changes, inspection backlogs, or interface constraints, project teams can prioritize mitigation actions and support fair claims management. Root-cause analysis should be performed at the system level rather than focusing only on direct labor behavior. [24,26]

Table 2. Comparative Productivity Diagnostic Techniques for Saudi Industrial Projects

Technique	Primary Purpose	Best Application	Value to Saudi Industrial Projects	References
Field Rating	Measure productive vs. non-productive time	Daily site productivity observation	Creates a baseline for crew and workfront performance assessment.	[21,23]
Work Sampling	Statistically quantify activity categories across crews	Large industrial sites with many simultaneous crews	Identifies hidden waiting, excessive movement, and support activity losses.	[23,38]
Five-Minute Rating (FMR)	Rapid field productivity diagnostic	Shutdowns, short-cycle work, immediate corrective feedback	Highlights productivity hotspots requiring quick management action.	[23,44]
Craftsman Questionnaire Sampling (CQS)	Explain why productivity losses occur through worker feedback	Multinational workforces and complex subcontractor environments	Captures field-level root causes often invisible to management dashboards.	[45]

Technique	Primary Purpose	Best Application	Value to Saudi Industrial Projects	References
Delay Modeling & Root-Cause Analysis	Attribute schedule loss to specific causal factors	Claims, recovery planning, lessons learned	Links productivity loss directly to schedule and financial impact.	[24,26]

5. Integrated Productivity Driver Framework for Industrial Projects


Construction productivity in industrial projects is multidimensional and system-driven. A decline in piping, steel, electrical, instrumentation, or civil productivity may be caused simultaneously by heat exposure, missing spools, scaffolding delays, crane unavailability, permit backlog, late inspections, poor work package readiness, excessive crew density, engineering changes, or subcontractor interface failures. Treating all productivity loss as a manpower problem can therefore lead to incorrect corrective action.

The integrated driver framework developed in this paper groups productivity constraints into environmental, technical, logistical, organizational, workforce, and workface-readiness dimensions. The objective is to provide project teams with a practical diagnostic structure for identifying dominant productivity drivers in their specific project context and selecting targeted mitigation measures. The framework is not a statistical multivariate model; it is a structured multi-factor diagnostic model intended for field use and future empirical validation.

The synthesis generates four core findings. First, productivity loss in Saudi industrial projects is frequently system-driven rather than craft-driven. Second, material readiness, engineering readiness, heat exposure, permit readiness, and workface constraints are recurring sources of non-productive time. Third, AWP, modularization, lean execution, BIM-enabled coordination, and digital workface-readiness systems address different but complementary mechanisms of productivity loss. Fourth, productivity governance should combine leading indicators such as IWP readiness, material kitting, and PPC with lagging indicators such as installed quantity per man-hour, rework hours, and schedule variance.

Figure 2 shows the diagnostic logic used to link observed productivity loss to root-cause classification, measurable field indicators, targeted mitigation, and governance feedback.

Productivity Diagnostic Logic: From Observed Loss to Corrective Action



Feedback loop: field evidence updates planning assumptions, readiness gates, and constraint-removal priorities.

Figure 2. Productivity Diagnostic Logic: From Observed Loss to Corrective Action

Table 3. Integrated Productivity Variables, Field Indicators, Impacts, and Mitigation Strategies

Variable	Typical Field Indicator	Likely Productivity Impact	Mitigation Strategy	References
Temperature & Humidity	Reduced afternoon output; increased rest cycles; heat incidents	Lower effective working time; elevated safety exposure	Night shifts, shaded work areas, hydration systems, WBGT-based heat-index scheduling.	[27,28]
Material Readiness	Crews waiting for spools, valves, supports, consumables	Idle time and out-of-sequence construction	AWP readiness gates, material kitting, digital tracking, laydown control.	[11,12,31,32,48-51]
Engineering Readiness	Late IFC drawings, open TQs, missing MTOs	Work stoppage, rework, costly resequencing	Construction-driven engineering, constructability reviews, EWP-CWP alignment.	[4,5,9,10,26]
Rework	Repeated welding, fit-up corrections, field modifications	Loss of man-hours and schedule disruption	Quality at source, improved supervision, design reviews, pre-inspection planning.	[10,23,24]
Crew Density	Congestion, access conflicts, inter-trade interference	Reduced productivity despite higher manpower	Area planning, modularization, resource leveling, workface control.	[17-20,23,25]
Logistics Reliability	Crane delays, transport bottlenecks, poor laydown	Interrupted field flow; fragmented workflows	Lift planning, scheduled delivery windows, logistics control tower.	[23-25,29,30]

Variable	Typical Field Indicator	Likely Productivity Impact	Mitigation Strategy	References
Ramadan & Cultural Calendar	Reduced working hours, altered shifts, night work adjustment	20–30% reduction in effective field hours during fasting month	<i>Advance schedule adjustment; Ramadan factors in baseline; night-shift optimization.</i>	[27,28,47]
Safety, PTW & SIMOPS	PTW delays, SIMOPS restrictions, incident investigations	Workflow disruption, permit backlogs, crew <i>demobilization</i>	Integrated safety-AWP planning, SIMOPS coordination, PTW pre-planning.	[7,23,24]

6. Strategic Mitigation Framework

6.1 Advanced Work Packaging (AWP)

Advanced Work Packaging (AWP) is one of the most important construction productivity methodologies available to large industrial projects. CII describes AWP as a construction-driven project delivery process that begins with the end in mind and integrates planning from early project definition through detailed design and field execution. [4,5,6] In practical terms, AWP ensures that engineering, procurement, construction, quality, safety, and commissioning are aligned around executable work packages rather than disconnected project milestones.

The central philosophy of AWP is that construction execution should drive the sequence of engineering and procurement deliverables. Traditional EPC models often release engineering based on discipline completion priorities rather than field installation sequence. This creates situations where drawings are available but materials are missing, materials are delivered but access is unavailable, or crews are mobilized before permits, scaffolding, tools, or inspections are ready. AWP reduces these disconnects by creating a structured pathway from construction strategy to workplace execution. [4,5,18]

A properly prepared Installation Work Package (IWP) should include IFC drawings, material status, permits, safety requirements, quality checkpoints, scaffolding needs, access requirements, inspection requirements, labor estimates, required tools, equipment allocation, and clear execution instructions. If any major constraint is unresolved, the package should not be released to the field.

Key implementation principles for AWP in KSA industrial projects include:

- Start AWP during FEED or early detailed engineering, not after construction mobilization.
- Define the Path of Construction before engineering and procurement priorities are frozen.
- Use integrated EPC planning workshops rather than isolated discipline planning sessions.
- Maintain a live constraint register linked to all active IWPs.
- Verify material readiness before each IWP is released to the field.

- Assign dedicated workforce planners with field construction experience.
- Integrate AWP with digital progress measurement and project controls systems from project outset.

Table 4. Advanced Work Packaging Elements and Productivity Contributions

AWP Element	Purpose	Productivity Contribution	References
Path of Construction	Defines the physical sequence in which the facility will be built.	Aligns engineering and procurement deliverables with field installation priorities.	[4-6]
Construction Work Area (CWA)	Divides project into manageable physical or logical execution areas.	Improves area control, resource allocation, and reduces crew congestion.	[4-6]
Engineering Work Package (EWP)	Groups engineering deliverables by construction need and sequence.	Reduces late drawing releases and design-interface delays.	[4-6]
Construction Work Package (CWP)	Groups construction scope by area, discipline, or system.	Improves planning accuracy, estimating, and field resource allocation.	[4-6]
Installation Work Package (IWP)	Provides short-duration, constraint-free field execution package.	Improves crew readiness and <u>can</u> reduces waiting time at workplace.	[4-6]
Constraint Log	Systematically tracks unresolved blockers before package release.	Prevents premature crew <u>mobilization</u> to unready workfronts.	[4,5]

Table 5. CII-Reported Productivity Improvement Ranges and Expected Effects of Mature AWP Implementation

Performance Area	CII-Reported Range	Practical Comment	Key Condition	References
Labor productivity	10–25% improvement	Most visible when IWPs are constraint-free and material-ready before <u>mobilization</u> .	Mature AWP + workforce planning discipline	[4,5]
Crew idle time	15–20% reduction	Waiting decreases when permits, materials, drawings, and access are pre-verified.	Active constraint log management	[4,5]
Schedule reliability	Improvement in PPC	Weekly planning becomes measurably more reliable and predictable.	Pull planning + lean integration	[4,5]
Material coordination	Significant improvement	Material availability is directly linked to work package release gates.	Digital material tracking	[4,5]

Performance Area	CII-Reported Range	Practical Comment	Key Condition	References
Engineering alignment	Moderate improvement	Engineering priorities become construction-driven from early project stages.	EWP-CWP integration from FEED	[4,5]
Administrative burden	Possible initial increase	Can occur if AWP becomes documentation-heavy without field discipline improvement.	Requires management commitment	[4,5]

Note: CII RT-272 (2015) and RT-319 (2019) report that projects with mature AWP implementation achieve 10–25% improvement in labor productivity and 15–20% reduction in crew idle time. Benefits are contingent on contractor maturity, digital integration, and senior management commitment. [4,5]

6.2 Modularization and Industrialized Construction

Modularization is a major productivity strategy for industrial projects because it transfers substantial construction scope from exposed, congested, and weather-sensitive field sites to controlled fabrication environments. While often discussed as a construction technique, modularization is better understood as a project delivery strategy affecting engineering, procurement, fabrication, logistics, contracting, quality, safety, commissioning, schedule, and total installed cost. [16,17,18,19,20]

In industrial projects, modularization may include pipe rack modules, process skids, utility modules, electrical substations, control rooms, compressor packages, preassembled piping systems, modular analyzer shelters, integrated equipment packages, and structural assemblies. The principal objective is to reduce onsite work volume, improve productivity stability, minimize field congestion, reduce exposure to extreme heat, and accelerate schedule execution.

Key modularization benefits for KSA industrial projects include:

- Reduction of onsite labor density and workforce accommodation demand.
- Lower craft exposure to extreme heat and humidity during peak summer periods.
- Improved fabrication productivity in controlled, weather-independent shop environments.
- Reduced field welding, scaffolding, and elevated work exposure and associated safety risk.
- Improved quality control, dimensional accuracy, and systematic inspection efficiency.
- Parallel execution of offsite fabrication and onsite civil and foundation work, enabling schedule compression.
- Reduced inter-trade interference between civil, mechanical, electrical, and commissioning activities on site.

The value of modularization should be evaluated through total installed cost (TIC) and lifecycle schedule impact rather than fabrication cost alone. Modularization may increase early

engineering hours, fabrication coordination effort, logistics cost, and heavy-lift complexity, but these increases are frequently offset by reduced field labor requirements, shorter site duration, lower rework rates, improved safety outcomes, and earlier mechanical completion. [18,19,22]

Brownfield facilities provide a particularly strong business case for modularization because site congestion, operating unit restrictions, permit controls, and shutdown windows often severely limit field productivity. Typical brownfield modular applications include replacement pipe racks, electrical substations, compressor auxiliary skids, utility tie-in modules, analyzer shelters, prefabricated pipe spools, and control buildings. Existing field conditions should be verified through laser scanning, 3D modeling, and dimensional control to avoid misalignment during module installation. [11,12]

Table 6. Modularization Planning Considerations for Saudi Industrial Projects

Planning Area	Key Question	Engineering Impact	References
Module envelope	What maximum size and weight can be transported by land or sea?	Controls module dimensions, structural reinforcement, split lines, and shipping fixtures.	[18,19,25]
Fabrication yard	Can the selected yard deliver required quality, capacity, and schedule?	Affects productivity, QA/QC standards, subcontracting, and logistics risk.	[18,19]
Transport route	Are ports, roads, bridges, clearances, and turning radii suitable?	May limit module size, require route modifications, or necessitate special permits.	[18,19,25]
Heavy lift	Are cranes, foundations, ground bearing, and lift corridors suitable?	Controls installation sequence, temporary works, and crane positioning strategy.	[18,19,25]
Stick-built interfaces	How will modules connect precisely to remaining stick-built scope?	Requires tight dimensional control, survey verification, and tie-in management.	[11,12,18,19]
Commissioning	Can vendor pre-commissioning and testing be partly completed offsite?	Improves schedule compression but requires preservation and vendor coordination.	[18,19,25]

Table 7. Comparison of Stick-Built and Modular Construction Approaches

Evaluation Dimension	Stick-Built Approach	Modular Approach	References
Engineering effort	Lower early engineering definition pressure.	Higher front-end definition and interface control required from FEED.	[18,19,22]

Evaluation Dimension	Stick-Built Approach	Modular Approach	References
Field labor demand	High onsite manpower demand throughout.	Significantly reduced onsite manpower; shop labor replaces field labor.	[18,19,22]
Climate exposure	High exposure to heat, humidity, dust, and wind.	Lower exposure due to controlled shop fabrication environment.	[27,28]
Quality control	Variable field conditions; site-supervision dependent.	Improved controlled fabrication environment; systematic QC achievable.	[18,19,22]
Logistics complexity	Simpler material shipments; conventional procurement.	Complex module transport, heavy-lift planning, and logistics engineering.	[18,19,25]
Schedule approach	Sequential field work dominates critical path.	Parallel offsite fabrication and site preparation enables compression.	[18,19,22]
Risk profile	Field productivity, congestion, and weather delay risk.	Interface, dimensional tolerance, transport, and heavy-lift risk.	[18,19,22,25]
Cost profile	Lower early engineering cost; higher field labor cost.	Higher early definition cost; lower field labor and site duration cost.	[18,19,22]

6.3 Lean Execution and Workflow Optimization

Lean execution in industrial construction is a practical operating philosophy focused on improving flow, removing constraints, reducing waste, and increasing the reliability of field execution. Lean construction literature consistently emphasizes that productivity is strongly linked to workflow reliability rather than labor intensity alone. [1,2,3,13,14,15]

For KSA industrial projects, lean execution is especially valuable because harsh climate conditions, large and diverse workforces, imported materials with long lead times, and complex interfaces between multiple organizations create frequent and compounding disruptions. Lean methods provide a disciplined approach to identifying problems early, stabilizing work sequences, and improving collaboration across engineering, procurement, construction, quality, safety, and commissioning functions.

The seven construction waste categories most relevant to Saudi industrial project environments include:

- Waiting: crews waiting for drawings, materials, permits, tools, inspections, or access.
- Motion: excessive walking, searching, climbing, or movement between scattered workfronts.
- Transportation: repeated movement of materials due to poor laydown planning or sequencing.

- Inventory: excessive onsite materials not aligned with active construction sequence.
- Rework: correction of defects arising from design changes, poor fit-up, or inadequate supervision.
- Overprocessing: unnecessary approvals, duplicated reporting, or excessive administrative handoffs.
- Underutilized knowledge: failure to involve field supervisors and craft personnel in near-term planning.

The Last Planner System improves planning reliability by shifting emphasis from theoretical schedule activities to reliable commitments made by the people responsible for field execution. It uses pull planning, look-ahead planning, constraint removal, weekly work planning, and Percent Plan Complete (PPC) measurement to improve near-term work reliability. [1,13,16]

Table 8. Lean Construction Methods and Expected Benefits for KSA Industrial Projects

Lean Method	Practical Application in KSA Context	Expected Benefit	References
Pull planning	Plan backwards from milestones and system turnover; engage multidisciplinary teams.	Improves sequence logic, exposes interface conflicts early, strengthens team alignment.	[1,13,16]
Look-ahead planning (3–6 weeks)	Screen work planned for upcoming weeks; identify and remove constraints before <i>mobilization</i> .	Identifies blockers before crews are mobilized to unready workfronts.	[1,13,16]
Weekly work planning	Commit only to activities that are genuinely executable with confirmed readiness.	Improves planning reliability, accountability, and Percent Plan Complete scores.	[1,13,16]
Percent Plan Complete (PPC)	Measure the proportion of weekly commitments actually completed; analyze variance reasons.	Identifies planning reliability trends and systemic constraint patterns.	[1,13,16]
Short-interval control	Daily or shift-based progress and constraint reviews at crew and supervisor level.	Enables fast corrective action before productivity losses compound.	[13,14]
Visual management	Physical dashboards, area boards, 3D model displays, color-coded workfront status.	Improves field-level communication, situational awareness, and decision speed.	[11,12,31,32,48-51]

6.4 Climate-Adaptive Management Protocols

Climate-adaptive management should be embedded into KSA project baseline planning from FEED onward, not introduced reactively during construction. This includes seasonal productivity factors incorporated into the project schedule, WBGT-based work-rest cycle protocols, night-shift planning and cost modeling, shaded work area design, cooling stations, hydration systems, heat-stress training programs, and specific supervision procedures for high-risk activities in extreme conditions. Heavy labor activities should be systematically sequenced to avoid peak thermal periods where practicable, particularly for scaffolding, steel erection, refractory work, insulation, and manual material handling. Ramadan productivity factors should be explicitly modeled in schedule baselines for all project phases. [27,28]

6.5 Supply-Chain Resilience and Material Management

Supply-chain resilience in KSA industrial projects requires systematic integration of procurement, logistics, laydown management, material kitting, and workface planning. Local sourcing partnerships for standard bulk materials, early vendor engagement for long-lead equipment, advance customs clearance planning, digital material tracking systems, and logistics control towers can substantially reduce field interruptions caused by material shortages. [29,30]

Material management must be treated as an active productivity control rather than a passive procurement function. Laydown areas should be planned and managed according to AWP sequence, kitting should be linked to IWP release gates, and material status should be visible to both project controls and field supervisors in real time. The goal is to ensure that every IWP released to the field has all required materials confirmed and accessible before crew mobilization.

6.6 Human Capital Development

Human capital development remains an essential and frequently underinvested dimension of productivity improvement in KSA industrial projects. Saudi industrial projects should invest systematically in technical training academies, field supervisor development programs, craft certification aligned with industry competency frameworks, multilingual and visual work instructions suited to multinational workforces, visual planning tools accessible at workface level, and structured knowledge transfer between experienced international specialists and developing Saudi talent. Workforce development directly supports KSA's Vision 2030 Saudization objectives while simultaneously improving safety performance, quality outcomes, and construction productivity. [47]

6.7 Digitalization Framework and Construction Productivity Optimization

The construction industry is increasingly adopting digital technologies to improve productivity, enhance project visibility, strengthen planning reliability, and support more effective project delivery. Building Information Modeling (BIM), digital twins, cloud-based collaboration platforms,

advanced analytics, drone-based monitoring, mobile field applications, and integrated project-controls systems provide opportunities to improve engineering coordination, construction execution, material management, and decision-making throughout the project lifecycle. [48-51] Digital process integration facilitates real-time connectivity between engineering, procurement, construction, quality, safety, and project-controls functions. By consolidating data from BIM models, scheduling systems, enterprise resource databases, field reports, drone surveys, IoT sensors, and productivity monitoring tools, project teams can gain improved visibility of workforce readiness, material status, progress performance, and emerging execution risks before they translate into field delay. [48,49]

Advanced analytics and predictive schedule controls are increasingly relevant to construction productivity optimization. Historical productivity patterns, constraint logs, material-readiness data, progress records, and weather exposure data can be analyzed to forecast emerging delay risks and support proactive resource adjustment. These digital decision-support capabilities shift project management from reactive correction to early warning, helping teams identify unready workfronts before crews are mobilized. [48-51]

Digital dashboards support continuous performance monitoring by converting project data into actionable management information. When integrated with AWP, modularization, lean construction, Last Planner routines, and project controls, these systems provide a practical digitalization framework for improving workforce readiness, reducing waste, enhancing schedule reliability, and supporting evidence-based project execution across the full lifecycle. [48-51]

Figure 3 summarizes the digitalization layer as a governance mechanism for integrating design, schedule, material, field, permit, and productivity information.

Digitalization Framework for Workforce Readiness and Productivity Governance




Figure 3. Digitalization Framework for Workforce Readiness and Productivity Governance

7. Illustrative Application Scenarios for Saudi and GCC Industrial Projects

The following scenarios demonstrate how the integrated productivity framework can be applied in typical Saudi and GCC industrial project environments. They are deliberately presented as illustrative application scenarios rather than empirical case studies. They are based on professional practice experience and published industry practices and are intended to show how the framework can be used to diagnose constraints and select mitigation strategies.

No confidential project data, proprietary performance records, or named project information is disclosed. Any improvement descriptions should therefore be interpreted as expected or literature-supported productivity effects rather than independently verified before-and-after statistical results. Where project teams have access to actual work sampling, man-hour, PPC, IWP readiness, or installed-quantity datasets, these scenarios can be converted into formal empirical case studies.

7.1 Scenario A: Gas Processing Expansion – AWP and Workfront Readiness

A representative gas processing expansion project experienced significant productivity loss during early construction because piping, structural steel, and mechanical crews were repeatedly mobilized to workfronts where drawings, materials, scaffolding, or permits were incomplete. The project introduced AWP mid-construction, focusing on IWPs, a live constraint log, and structured material readiness reviews. Although implementation began later than optimal, workfront continuity improved in the illustrative scenario.

Table 9. Illustrative Scenario A: Gas Processing Expansion – AWP and Workfront Readiness

Case Parameter	Before AWP Implementation	After AWP Implementation	References
Work package release	Based mainly on schedule pressure regardless of workfront readiness.	Released only after formal readiness review against constraint log.	[4,5]
Material control	Materials present at site but not consistently kitted by work package.	Material kitting systematically linked to IWP release gates.	[4,5,29,30]
Crew idle time	Frequent waiting for scaffolding, permits, and missing spools.	<u>Can be</u> reduced through structured constraint screening.	[4,5,23]
Field supervision	Reactive daily troubleshooting; limited advance planning.	Planned execution with daily package review and look-ahead.	[4,5,23]
Productivity trend	Unstable and variable; frequent unplanned workfront interruptions.	More stable week-on-week with fewer unplanned interruptions.	[4,5]
Main lesson	Schedule pressure alone cannot create productivity.	Readiness-based work release is the primary driver of reliable field productivity.	[4,5,23]

7.2 Scenario B: Petrochemical Pipe Rack Expansion – Modularization

A representative petrochemical expansion adopted modular pipe rack construction to reduce field congestion and mitigate summer productivity loss. Pipe rack sections were fabricated offsite, preassembled with selected supports, cable tray provisions, and piping systems, then transported to site for heavy-lift installation. The strategy required early route studies, fabrication yard qualification, lifting engineering, and dimensional interface control.

Table 10. Illustrative Scenario B: Petrochemical Pipe Rack Expansion – Modularization

Case Aspect	Observed Approach	Value Added	References
Execution strategy	Offsite pipe rack module fabrication at a controlled fabrication yard.	Eliminated high-elevation field steel erection and reduced field welding exposure.	[17-20]
Climate mitigation	Shop fabrication conducted during peak summer months (June–August).	Significantly reduced direct labor exposure to extreme heat and humidity.	[27,28]
Schedule effect	Parallel site foundation work and module fabrication executed simultaneously.	<i>Can support</i> schedule compression versus sequential stick-built alternative.	[18,19,22]
Quality effect	Controlled fabrication with systematic dimensional inspection program.	Reduced fit-up problems and welding rework during final site installation.	[18,19]
Key challenge	Transportation route qualification and heavy-lift crane positioning.	Required early logistics engineering and route study investment during FEED.	[18,19,25]
Main lesson	Modularization must be decided and designed during concept or FEED stages.	Late decisions create costly redesign, interface risk, and schedule delay.	[18,19,25]

7.3 Scenario C: Refinery Shutdown Upgrade – Lean Execution

A representative refinery shutdown project applied lean execution methods during a high-density turnaround window. The project faced severe access limitations, simultaneous mechanical, piping, inspection, and commissioning activities across multiple units, and intense schedule pressure. Daily pull-planning sessions, rolling constraint tracking, logistics coordination meetings, and shift-based short-interval progress reviews can improve field coordination and reduce wasted movement.

Table 11. Illustrative Scenario C: Refinery Shutdown Upgrade – Lean Execution

Area	Initial Challenge	Lean Intervention	Outcome	References
Workfront congestion	Multiple trades competing for the same physical access space.	Area-based coordination and daily sequencing by discipline.	Reduced crew interference and improved workflow continuity.	[13,16,23]
Inspection backlogs	Completed work waiting extended periods for quality inspection.	Daily QC coordination meetings and rolling inspection look-ahead.	Faster turnover and reduced re-inspection cycles.	[13,16,24]
Material staging	Materials not consistently staged near the active workfront.	Dedicated kitting program and defined delivery windows per area.	Reduced searching, walking time, and unplanned crew movement.	[4,5,23,29,30]
Schedule control	Weekly schedule too coarse for the dynamic shutdown environment.	Shift-based short-interval control with daily progress reporting.	Faster identification of deviation and accelerated recovery.	[13,16]
Communication	Separate discipline planning; poor cross-discipline coordination.	Integrated daily planning meetings with all discipline leads.	Improved alignment, accountability, and inter-trade coordination.	[13,16]

7.4 Scenario D: Remote Utility Package Installation – Skid-Mounted Systems

A representative remote gas processing project used skid-mounted utility and process packages to reduce onsite labor demand and overcome remote-area workforce limitations. Packaged systems included chemical injection skids, instrument air packages, electrical rooms, and utility modules. Vendor-controlled fabrication reduced field installation complexity and can improve system readiness at mechanical completion.

Table 12. Illustrative Scenario D: Remote Utility Package Installation – Skid-Mounted Systems

<u>Parameter</u>	Conventional Field Build	<u>Skid / Module Strategy</u>	References
Labor demand	Large onsite multidisciplinary teams required throughout.	Significantly reduced site labor through vendor shop fabrication.	[18,19,22]
Quality control	Variable field welding and assembly conditions; site-dependent.	Vendor-controlled fabrication, systematic testing, and QC documentation.	[18,19,22]
Remote logistics	Many small material shipments requiring site assembly.	<i>Fewer, larger integrated package deliveries; simpler site installation.</i>	[18,19,25]

<i>Parameter</i>	Conventional Field Build	<i>Skid / Module Strategy</i>	References
Commissioning readiness	Extensive field testing and loop checks on site.	Partial vendor factory acceptance testing before shipment.	[18,19,25]
Productivity predictability	Highly sensitive to remote labor availability and site conditions.	More predictable installation productivity in remote environment.	[18,19,22]
Primary risk	Field labor availability and remote accommodation constraints.	Vendor interface quality, package integration, and transport.	[18,19,25]

7.5 Scenario E: Gas Processing Megaproject – Digitalization and BIM Integration

A representative large-scale gas processing megaproject integrated BIM, digital twin technology, drone-based progress monitoring, and AWP-linked digital dashboards across the full project lifecycle. The integration was planned from FEED and implemented progressively through detailed engineering, fabrication, and construction phases. Digital tools were connected to the project controls system to provide real-time workforce readiness data to both field supervisors and senior management.

Table 13. Illustrative Scenario E: Gas Processing Megaproject – Digitalization and BIM Integration

Digital Capability	Application	Productivity Contribution	References
BIM & 3D model integration	Clash detection, constructability reviews, module interface coordination.	Reduced field rework, improved installation accuracy, better access planning.	[11,12,48-50]
Digital twin	Virtual facility model synchronized with field progress and engineering data.	Enabled scenario analysis, proactive schedule management, faster decisions.	[48-50]
Drone-based progress monitoring	Weekly aerial surveys compared against 3D model baseline.	Objective, consistent progress data without manual quantity surveying delays.	[48-51]
AWP-integrated dashboards	Real-time IWP status, constraint log, material readiness, and PPC metrics.	Management visibility of workforce readiness before crew <i>mobilization</i> .	[4,5,48-51]
<u>Predictive schedule controls</u>	Historical productivity data used to forecast delay risks and <i>optimize</i> resources.	Proactive identification of emerging issues; improved baseline accuracy.	[48-51]
Mobile field applications	Supervisors capture progress, punch items, and RFIs directly from workforce.	Eliminated paper-based reporting delays; real-time integration with project controls.	[11,12,48-51]

8. Integrated Productivity Model: Combining AWP, Modularization, Lean Execution, and Diagnostics

AWP, modularization, lean execution, quantitative diagnostics, and digitalization tools should not be treated as separate or competing initiatives. Their greatest value is achieved when they operate as an integrated and mutually reinforcing productivity system. AWP defines and controls executable work packages; modularization reduces field scope and congestion; lean execution stabilizes daily workflow; productivity diagnostics reveal the root causes of non-productive time; and digitalization tools provide the data integration and visibility needed to manage the system in real time.

This integration is especially important in Saudi industrial projects where the productivity challenge is multidimensional, simultaneously involving climate stress, supply-chain risk, engineering readiness, interface complexity, workforce diversity, permit requirements, and subcontractor coordination. No single methodology is sufficient to address all of these dimensions. The integrated framework proposed in this paper provides a systematic structure for combining these approaches in a practical, measurable, and scalable way for industrial megaproject environments.

Figure 4 consolidates the implementation logic by showing how AWP, modularization, lean execution, diagnostic controls, and digitalization governance operate across project phases.

Integrated AWP, Modularization, Lean Execution, and Diagnostic Control Model




Figure 4. Integrated AWP, Modularization, Lean Execution, and Diagnostic Control Model

Table 14. Integration of AWP, Modularization, Lean Execution, Diagnostics, and Digitalization Tools

Methodology	Primary Role	Integration Benefit	References
AWP	Creates construction-driven, constraint-free work packages.	Ensures crews receive executable work with materials, drawings, permits, and access confirmed.	[4-6]
Modularization	Transfers scope offsite and reduces field complexity.	Improves productivity stability, reduces congestion, and lowers climate exposure.	[17-20,22]
Lean Execution	Stabilizes workflow and removes waste at crew and supervisor level.	Improves daily execution reliability through pull planning and short-interval control.	[1,13-16]
Work Sampling & CQS	Diagnoses the specific mechanisms of productivity loss.	Identifies whether losses are driven by labor, material, access, planning, or system failures.	[21,23]
Digital Tools & Analytics	Provides real-time visibility and integrated data across all project functions.	Enables real-time decision-making, predictive risk identification, and faster corrective action.	[11,12,31,32,48-51]
<u>Advanced analytics & predictive controls</u>	<u>Analyze historical and real-time project data to forecast delay risks and optimize resources.</u>	<u>Shifts management from reactive correction to early warning and proactive intervention.</u>	[48-51]

9. Implementation Roadmap for Saudi Industrial Projects

To convert productivity theory into measurable field improvement, KSA industrial projects should adopt a phased implementation roadmap beginning before construction mobilization and continuing through commissioning. The primary objective is to avoid the common and costly situation where productivity improvement is attempted only after delays have already accumulated. Early integration of construction engineering, AWP, modularization screening, lean execution planning, and productivity diagnostics provides the highest opportunity for cost and schedule benefit. [4,5,23,24]

During concept and FEED stages, owners and EPC contractors should define construction execution philosophy, modularization strategy, logistics constraints, heat-adaptive planning assumptions, Ramadan productivity factors, and preliminary Path of Construction. During detailed engineering, Engineering Work Packages should be aligned with construction priorities, long-lead procurement should be linked to installation sequences, and constructability reviews should be conducted with direct participation from construction supervisors, commissioning representatives, and logistics engineers. [11,18,25]

A practical implementation roadmap also requires clear ownership and accountability. AWP must not be owned only by planners; lean execution cannot be delegated only to quality teams; and modularization cannot be treated solely as a fabrication decision. These are integrated project

delivery strategies requiring active participation from project management, engineering, procurement, construction, quality, HSE, logistics, commissioning, key vendors, and principal subcontractors.

Table 15. Phased Implementation Roadmap for Productivity Optimization in Saudi Industrial Projects

Project Phase	Productivity Focus	Key Deliverables	References
Concept / FEED	Avoid costly late productivity decisions; establish execution philosophy.	Construction execution philosophy, modularization screening, preliminary Path of Construction, constructability plan, heat-adaptive planning assumptions, Ramadan productivity factors.	[4,5,18,23-25]
Detailed Engineering	Align design deliverables with construction priorities and sequences.	EWPs aligned to CWP, 3D model constructability reviews, lift studies, access planning, procurement sequencing by installation priority.	[4,5,11,18,25]
Procurement & Fabrication	Protect material readiness and module fabrication quality.	Vendor schedule tracking, module fabrication plan, kitting strategy, logistics control, customs clearance planning.	[18,19,29,30]
Construction <u>Mobilization</u>	Release only genuinely executable work packages to the field.	CWPs, IWPs with full readiness verification, constraint register, readiness gates, manpower and equipment <u>mobilization</u> plan.	[4,5,23]
Execution & Monitoring	Control daily productivity losses; maintain workforce readiness.	Work Sampling, CQS, short-interval control, daily coordination meetings, lean dashboards, KPI reporting.	[11,12,31,32,48-51]
Pre-Commissioning	Protect system completion sequence and punch list closure.	System turnover packages, punch closure plan, preservation inspection, vendor support coordination.	[23-25]

10. Value Engineering, Constructability, and Construction Engineering Integration

In industrial construction, Value Engineering (VE) should not be limited to cost reduction. It should evaluate construction method, site congestion, modularization potential, material substitution, maintainability, safety performance, commissioning sequence, and total installed cost. A lower material or fabrication cost may not represent best value if it increases field labor requirements, rework probability, scaffolding demand, crane utilization, or shutdown duration. [24,25,26]

Constructability is one of the most powerful productivity levers available before field execution begins. Many productivity losses are created during design through congested plot plans, difficult access arrangements, excessive field welding requirements, poor module split lines, complex

temporary works, inadequate lifting access, and insufficient consideration of installation sequence. Formal constructability reviews during FEED and detailed engineering allow project teams to eliminate these barriers before they become costly field delays. [23,24,25]

Key constructability review activities for KSA industrial projects include:

- Construction-driven plot plan reviews to confirm crane access corridors, laydown areas, module transport routes, maintenance access, and equipment installation paths.
- Heavy lift and temporary works reviews to confirm crane capacity, ground bearing pressure, lifting point locations, rigging studies, and installation sequence logic.
- 3D model reviews with construction, operations, commissioning, and subcontractor participation to identify clashes, access restrictions, and maintainability concerns.
- Field welding minimization through spool optimization, prefabrication strategies, and improved shop fabrication planning.
- Commissioning-driven system completion planning to ensure mechanically complete areas can be tested, energized, and turned over efficiently.

Construction engineering integration is particularly critical in Saudi industrial projects where remote sites, extreme weather, long logistics chains, and brownfield operational interfaces can amplify the consequences of poor constructability decisions made during engineering. A strong construction engineering function should include specialists in constructability, workface planning, temporary works, heavy lifts, scaffolding strategy, logistics engineering, equipment preservation, and modular execution.

11. Practical Productivity Governance and KPI System

A comprehensive productivity improvement program requires sustained governance from senior project management. Senior management should receive productivity information that clearly distinguishes between direct labor inefficiency and systemic planning or supply-chain constraints. A dashboard showing only earned value progress may not reveal whether crews are waiting for materials, walking long distances to scattered workfronts, working without complete drawings, or being disrupted by permit and inspection backlogs. A professionally designed productivity governance system combines leading and lagging indicators to provide actionable management insight. [7,23,30]

Table 16. Practical Productivity Governance and KPI System for Saudi Industrial Projects

KPI Category	Example Indicator	Management Use	References
Workface readiness	% of IWPs released without open constraints.	Measures whether crews are consistently given executable, constraint-free work packages.	[4,5,23]

KPI Category	Example Indicator	Management Use	References
Material readiness	% of required materials kitted and available by work package.	Predicts workforce interruption risk before crew <i>mobilization</i> occurs.	[4,5,29,30]
Engineering readiness	IFC drawing availability and TQ closure rate by construction sequence.	Confirms design deliverables support active field priorities.	[9,10,26]
Labor productivity	Installed quantity per man-hour by discipline and work area.	Tracks output efficiency as a lagging indicator after readiness is confirmed.	[21,23]
Non-productive time (NPT)	Waiting, walking, searching, idle time proportion from Work Sampling.	Identifies hidden productivity losses and root causes for targeted corrective action.	[21,23,38]
Planning reliability (PPC)	Percent Plan Complete and reasons for weekly commitment variance.	Measures planning reliability and effectiveness of constraint removal.	[1,13,16]
Climate exposure	Lost productive hours or productivity reduction factor by heat-index period.	Supports climate-adaptive scheduling and proactive workforce protection planning.	[27,28]
Rework rate	Rework man-hours as % of total man-hours by trade and work area.	Identifies quality and supervision issues; links rework cost to causal factors.	[10,23,24]
Subcontractor performance	Subcontractor PPC, IWP completion rate, and safety compliance.	Enables multi-tier subcontractor management and performance accountability.	[7,23,24]

The KPI system should be structured to avoid incorrectly attributing system failures to workforce performance. If Work Sampling and CQS evidence shows that crews are waiting for spools, access, permits, or inspection completion, the corrective action must target planning, logistics, work package readiness, or supervision — not simply increasing manpower. This distinction is essential for professional productivity management and for maintaining workforce morale, trust, and sustained engagement in a multinational project environment.

12. Framework Implementation Risk Matrix

Effective implementation of the integrated productivity framework requires proactive identification and management of the most likely failure modes. The following risk matrix identifies the primary implementation risks for AWP, Lean Execution, and Modularization in the KSA industrial project context, together with recommended mitigation approaches.

Table 17. Implementation Risk Matrix for the Integrated Productivity Framework

Framework Element	Primary Failure Mode	Risk Level	Recommended Mitigation	References
AWP	Documentation-heavy implementation without real constraint removal at workforce.	High	Assign experienced workforce planners; tie IWP release strictly to constraint log closure; measure PPC.	[4,5,23]
AWP	Late start – AWP introduced after construction <i>mobilization</i> .	High	Mandate AWP planning gate in EPC contract from FEED; include in contractor prequalification.	[4,5]
Lean Execution	Pull planning treated as one-time workshop rather than sustained daily discipline.	Medium	Embed lean planning in supervisory KPIs; provide ongoing coaching; measure PPC weekly.	[1,13,16]
Lean Execution	Cultural resistance to collaborative planning in hierarchical contract environments.	Medium	Senior leadership visible commitment; cross-discipline facilitation; demonstrate early wins.	[13,14]
Modularization	Late modularization decision after detailed design is advanced.	High	Establish strategy during concept/FEED; include transport and lifting studies before IFD issue.	[18,19,25]
Modularization	Fabrication yard capability gap or quality failure.	High	Rigorous yard qualification; early engagement; third-party inspection; ASME/ISO-aligned QC plan.	[18,19]
Digitalization	Data silos – BIM, scheduling, and field reporting not integrated.	Medium	Mandate common data environment (CDE) in EPC contract; integrate AWP software with project controls from Day 1.	[48-51]
Climate Adaptation	Ramadan and peak summer not factored into baseline schedule.	Medium-High	Include Ramadan productivity factors in schedule baseline at FEED; update with calendar projections annually.	[27,28,47]

13. Strategic Recommendations for KSA Industrial Projects

Based on the integrated assessment presented in this paper, productivity optimization should be treated as an integrated project delivery objective rather than a construction-phase concern. The following recommendations are prioritized for KSA industrial project owners, EPC contractors, and project management organizations:

1. Start productivity planning during FEED, not after construction mobilization. Every month of delay in AWP and constructability planning has compounding field execution consequences.
2. Adopt AWP as a construction-driven execution philosophy embedded in contract requirements, not merely a documentation system implemented by planners in isolation.
3. Define the Path of Construction before engineering and procurement priorities are frozen. This single decision aligns the entire delivery chain around field execution sequence.
4. Evaluate modularization during concept selection and FEED using total installed cost and schedule risk analysis, not fabrication unit cost alone.
5. Explicitly model Ramadan productivity factors and peak summer heat-impact factors in the project schedule baseline from FEED. Do not rely on float to absorb these predictable impacts.
6. Integrate materials management with IWP readiness gates and workface planning. Procurement status is not the same as material readiness at the workface.
7. Use Work Sampling, Five-Minute Rating, CQS, and delay modeling to diagnose productivity loss with evidence. Avoid attributing system failures to workforce performance without data.
8. Use digital dashboards integrating AWP, BIM, scheduling, materials, permits, and workface-readiness data to monitor engineering readiness, material readiness, constraint status, and field productivity in real time.
9. Develop and resource construction engineering capability in constructability, heavy lift engineering, logistics, temporary works, workface planning, and modular execution.
10. Invest in technical training, supervisor development, and craft certification to support Saudi workforce development and Vision 2030 Saudization objectives while improving site performance.
11. Apply the KPI governance framework (Table 16) to distinguish system constraint failures from labor efficiency issues, and direct corrective actions accordingly.

14. Discussion, Limitations, Future Research, and Conclusions

14.1 Discussion and Contribution

This paper addresses the practical and scholarly gap created by fragmented treatment of construction productivity drivers in Saudi industrial projects. Rather than treating climate, labor, engineering, procurement, materials, AWP, modularization, lean execution, and digitalization as separate topics, the paper integrates them into a field-oriented diagnostic and mitigation framework. The main contribution is a structured model that links productivity loss mechanisms to measurable indicators, diagnostic methods, mitigation levers, implementation risks, and KPI-based governance.

The framework reinforces an important conclusion for industrial project management: productivity loss is often system-driven rather than craft-driven. Crews cannot achieve sustained productivity when drawings are incomplete, materials are unavailable, permits are delayed, scaffolding is missing, inspections are backlogged, access is restricted, or work packages are released before constraints are removed. The framework therefore shifts the productivity discussion from manpower addition to workplace readiness, workflow reliability, construction-driven planning, and disciplined governance.

14.2 Practical Implications

For owners, EPC contractors, construction managers, and subcontractors, the practical implication is that productivity planning must begin during concept and FEED stages. AWP, modularization screening, logistics planning, heat-adaptive scheduling, Ramadan productivity factors, constructability review, material kitting, and digital workplace dashboards should be embedded before construction mobilization. During execution, work sampling, Five-Minute Rating, CQS, PPC, IWP readiness, material readiness, rework tracking, and delay-cause coding should be used to distinguish labor inefficiency from systemic constraint failure.

14.3 Limitations

This study is limited by its reliance on literature synthesis, recognized industry guidance, and illustrative practice scenarios rather than a project-level productivity dataset. The proposed framework has not been statistically tested using multi-project observations, regression models, SEM, factor analysis, ANOVA, Bayesian modelling, or other quantitative techniques. Consequently, the framework should not be interpreted as proof of causal effectiveness. It is a structured diagnostic and mitigation framework intended for practice application and future empirical validation.

A second limitation is regional specificity. The framework is designed for Saudi and GCC industrial construction contexts, where extreme climate, imported supply chains, multinational workforces, EPC interfaces, PTW/SIMOPS controls, and Vision 2030-linked industrial growth are especially relevant. Some principles are transferable to other regions, but implementation priorities and productivity loss mechanisms may differ in different regulatory, labor-market, contractual, and climatic environments.

14.4 Future Research

Future studies should validate the proposed framework using real project datasets from Saudi industrial construction projects. Suitable variables include work sampling observations, direct/support/non-productive time proportions, WBGT or heat-index exposure, material kitting status, IWP constraint-free release, IFC drawing availability, TQ/RFI closure, permit readiness, PPC, rework man-hours, installed quantities, man-hours, discipline-level productivity rates, delay causes, and schedule variance. These data could support regression analysis, correlation analysis,

ANOVA, factor analysis, SEM, Bayesian modelling, clustering, or predictive analytics to quantify relationships between readiness variables and productivity outcomes.

Future research should also compare the productivity impact of early versus late AWP adoption, modular versus stick-built execution, manual versus digitally integrated material tracking, and baseline schedules with or without explicit heat and Ramadan productivity factors. Such research would move the field from framework synthesis toward statistically validated productivity governance models for Saudi industrial megaprojects.

14.5 Conclusion

Construction productivity in KSA industrial projects is shaped by an interdependent set of constraints: climatic exposure, supply-chain reliability, workforce capability, engineering readiness, field logistics, cultural calendar effects, safety and permit systems, subcontractor performance, construction methodology, and management discipline. Traditional approaches that focus mainly on increasing manpower are insufficient because many productivity losses arise from unstable workflow, incomplete workfronts, material shortages, engineering changes, rework, inspection delays, permit delays, and poor planning integration.

The integrated framework developed in this paper provides a practical basis for diagnosing and mitigating these productivity losses. AWP aligns engineering, procurement, construction, quality, safety, and commissioning around executable work packages. Modularization reduces onsite labor intensity and climate exposure by transferring appropriate scope to controlled fabrication environments. Lean execution improves workflow reliability through pull planning, look-ahead planning, PPC, short-interval control, and constraint removal. BIM-enabled coordination, digital dashboards, advanced analytics, and predictive schedule controls improve visibility and support faster corrective action.

As Saudi Arabia continues to execute large and complex industrial and infrastructure developments, construction productivity will remain a critical determinant of cost, schedule, safety, quality, and strategic industrial performance. Organizations that integrate construction-driven planning, modular execution, lean workflow management, climate-adaptive scheduling, BIM-enabled digitalization, workforce capability development, and KPI-based governance will be better positioned to deliver industrial projects reliably and competitively.

Abbreviations and Acronyms

Abbreviation	Definition	Abbreviation	Definition
<u>CDE</u>	<u>Common Data Environment</u>	IFC	Issued for Construction
AWP	Advanced Work Packaging	IoT	Internet of Things
BIM	Building Information Modeling	IWP	Installation Work Package
CII	Construction Industry Institute	KPI	Key Performance Indicator

Abbreviation	Definition	Abbreviation	Definition
CPI	Chemical Process Industry	KSA	Kingdom of Saudi Arabia
CQS	Craftsman Questionnaire Sampling	LNG	Liquefied Natural Gas
CWA	Construction Work Area	MTO	Material Take-Off
CWP	Construction Work Package	PPC	Percent Plan Complete
DCS	Distributed Control System	PTW	Permit to Work
EPC	Engineering, Procurement and Construction	QA/QC	Quality Assurance / Quality Control
EWP	Engineering Work Package	SIMOPS	Simultaneous Operations
FEED	Front-End Engineering Design	TIC	Total Installed Cost
FMR	Five-Minute Rating	TQ	Technical Query
GCC	Gulf Cooperation Council	VE	Value Engineering
HSE	Health, Safety and Environment	WBGT	Wet Bulb Globe Temperature

Bibliography

1. Ballard, G. (2000). The Last Planner System of Production Control. PhD thesis, University of Birmingham.
2. Koskela, L. (1992). Application of the New Production Philosophy to Construction. Stanford University, Center for Integrated Facility Engineering.
3. Howell, G. A. (1999). What Is Lean Construction? Proceedings of the 7th Annual Conference of the International Group for Lean Construction (IGLC-7), Berkeley, CA.
4. Construction Industry Institute (CII). (2015). Making the Case for Advanced Work Packaging as a Standard Best Practice. Research Summary 272-1, Austin, TX: CII.
5. Construction Industry Institute (CII). (2019). Validating Advanced Work Packaging as a Best Practice. Research Summary 319-1, Austin, TX: CII.
6. CII. (2020). AWP-CBA Education Framework: Advanced Work Packaging Certification Body of Knowledge. Austin, TX: Construction Industry Institute.
7. Project Management Institute. (2021). A Guide to the Project Management Body of Knowledge (PMBOK Guide), 7th ed. Newtown Square, PA: PMI.
8. Hanna, A. S., Taylor, C. S., & Sullivan, K. T. (2005). Impact of extended overtime on construction labor productivity. *Journal of Construction Engineering and Management*, 131(6), 734-739.
9. Thomas, H. R., & Horman, M. J. (2006). Fundamental principles of workforce management. *Journal of Construction Engineering and Management*, 132(1), 97-104.

10. Love, P. E. D., Edwards, D. J., & Smith, J. (2016). Rework causation in industrial construction projects. *Engineering, Construction and Architectural Management*, 23(4), 510-526.
11. Eastman, C., Teicholz, P., Sacks, R., & Liston, K. (2018). *BIM Handbook*, 3rd ed. Hoboken, NJ: Wiley.
12. Teizer, J., Cheng, T., & Fang, Y. (2013). Location tracking and data visualization technology to advance construction safety and productivity. *Automation in Construction*, 35, 572-582.
13. Ballard, G., & Tommelein, I. (2021). 2020 Current Process Benchmark for the Last Planner System. *Lean Construction Journal*, 17, 57-91.
14. Salem, O., Solomon, J., Genaidy, A., & Minkarah, I. (2006). Lean construction: From theory to implementation. *Journal of Management in Engineering*, 22(4), 168-175.
15. Abdelhamid, T. (2004). The self-destruction and renewal of lean construction theory. *Lean Construction Journal*, 1(1), 1-17.
16. Hamzeh, F. R. (2011). The lean journey: Implementing the Last Planner System in construction. *Proceedings of the 19th Annual Conference of the IGLC*, Lima, Peru.
17. Bertelsen, S. (2005). Modularization – A third approach to making construction lean? *Proceedings of the 13th Annual Conference of the IGLC*, Sydney, Australia.
18. Bondi, A., Magagnini, A., Mancini, M., Micheli, G. J. L., & Travaglini, A. (2016). Supporting decisions on industrial plant modularization: A case study in oil and gas. *Proceedings of the 6th IEOM Conference*, Detroit, MI.
19. Tak, A. N., Taghaddos, H., Mousaei, A., & Hermann, U. (2020). Evaluating industrial modularization strategies: Local versus overseas fabrication. *Automation in Construction*, 109, 102999.
20. Taku, A. M. (2021). Predicting Modular Efficiency in Oil and Gas Capital Projects. Unpublished doctoral dissertation.
21. Aldossary, H. E. (2024). Modularization in gas processing facilities: Planning considerations and execution strategies. *PM World Journal*, XIII(IV). <https://pmworldlibrary.net/wp-content/uploads/2024/03/pmwj139-Mar2024-Aldossary-Modularization-in-gas-processing-facilities.pdf>
22. Ikpe, E., & Omuh, I. (2014). Analysis of modularization compared to total project cost in Alberta oil and gas construction. *Global Advanced Research Journal of Engineering*, 3(3), 088-097.
23. Oglesby, C. H., Parker, H. W., & Howell, G. A. (1989). *Productivity Improvement in Construction*. New York, NY: McGraw-Hill.
24. Halpin, D. W., & Senior, B. A. (2010). *Construction Management*, 4th ed. Hoboken, NJ: Wiley.
25. Peurifoy, R. L., Schexnayder, C. J., & Shapira, A. (2018). *Construction Planning, Equipment, and Methods*, 9th ed. New York, NY: McGraw-Hill.
26. Kerzner, H. (2022). *Project Management: A Systems Approach to Planning, Scheduling, and Controlling*, 13th ed. Hoboken, NJ: Wiley.
27. Occupational Safety and Health Administration (OSHA). (2017). *OSHA Technical Manual: Heat Stress*. Washington, DC: U.S. Department of Labor. Retrieved from <https://www.osha.gov/otm/section-3-health-hazards/chapter-4>

28. International Labour Organization (ILO). (2019). Working on a Warmer Planet: The Impact of Heat Stress on Labour Productivity and Decent Work. Geneva, Switzerland: ILO.
29. World Bank. (2023). Logistics Performance Index. Washington, DC: The World Bank Group. Retrieved from <https://lpi.worldbank.org>
30. McKinsey & Company. (2020). The Next Normal in Construction: How Disruption Is Reshaping the World's Largest Ecosystem. New York, NY: McKinsey Global Institute.
31. Deloitte. (2021). Future of Construction: A Global Forecast for Construction to 2030. London, UK: Deloitte Insights.
32. Autodesk Construction Cloud. (2022). State of the Industry 2022: Trust and Technology in Construction. San Francisco, CA: Autodesk.
33. Society of Petroleum Engineers (SPE). Technical papers on modular construction and megaproject delivery. Retrieved from <https://www.onepetro.org>
34. Hydrocarbon Processing. Technical articles on project execution and construction productivity. Retrieved from <https://www.hydrocarbonprocessing.com>
35. GCC Statistical Centre (GCC-STAT). (2023). GCC Unified Economic Report. Riyadh, Saudi Arabia: Gulf Cooperation Council Statistical Centre.
36. Saudi Aramco. Engineering standards, project execution practices, and industrial construction guidance (publicly available references). Dhahran, Saudi Arabia.
37. ASCE. Construction Research Congress proceedings on industrial construction productivity and project performance. Retrieved from <https://ascelibrary.org>
38. Formoso, C. T., Isatto, E. L., & Hirota, E. H. (1999). Method for waste control in the building industry. Proceedings of the 7th Annual Conference of the IGLC, Berkeley, CA.
39. Aziz, R. F., & Hafez, S. M. (2013). Applying lean thinking in construction and performance improvement. Alexandria Engineering Journal, 52(4), 679-695.
40. Daniel, E. I., Pasquire, C., & Dickens, G. (2015). Exploring the implementation of the Last Planner System through IGLC conference literature. Proceedings of the 23rd IGLC Conference, Perth, Australia.
41. Alzara, M. (2022). Exploring the impacts of change orders on the performance of construction projects in KSA. Advances in Civil Engineering, 2022, Article 3168724.
42. Mahamid, I., Al-Ghonamy, A., & Aichouni, M. (2014). Major factors influencing employee productivity in the KSA public construction projects. International Journal of Civil & Environmental Engineering, 14(2), 16-20.
43. Azmi, N. A., Salleh, N. A., Zakaria, R., & Yahya, M. Y. (2022). Exploring blockchain technology for construction supply-chain management in the Saudi Arabian construction industry. Buildings, 12(11), 1858.
44. Chang, S., Yi, J.-S., & Son, J. (2015). Productivity improvement for steel framing work efficiency by Work Sampling and Five-Minute Rating. Journal of Construction Engineering and Project Management, 5(1), 40-46.

45. Chang, L.-M., & Borchering, J. D. (1985). Evaluation of Craftsman Questionnaire Sampling for construction productivity analysis. *Journal of Construction Engineering and Management*, 111(4), 396-405.
46. Mahamid, I. (2022). Relationship between delay and productivity in construction projects. *International Journal of Advanced and Applied Sciences*, 9(2), 160-166.
47. Government of Saudi Arabia. (2016). Saudi Vision 2030 Program. Riyadh, Saudi Arabia. Retrieved from <https://www.vision2030.gov.sa>
48. International Organization for Standardization. (2018). ISO 19650-1:2018: BIM – Information Management – Part 1: Concepts and Principles. Geneva, Switzerland: ISO.
49. International Organization for Standardization. (2018). ISO 19650-2:2018: BIM – Information Management – Part 2: Delivery Phase of the Assets. Geneva, Switzerland: ISO.
50. Borrmann, A., König, M., Koch, C., & Beetz, J. (Eds.). (2018). *Building Information Modeling: Technology Foundations and Industry Practice*. Cham, Switzerland: Springer.
51. Whyte, J. K., & Hartmann, T. (2017). How digitizing building information transforms the built environment. *Building Research & Information*, 45(6), 591-595.

About the Authors



Saad A. Al-Wahaib

Kingdom of Saudi Arabia



Saad A. Al-Wahaib, M.E. CEM, PMP is a Supervisor Project Engineer with over 15 years of professional experience in the oil and gas sector, specifically in project management across various project phases from detailed engineering through construction, in both greenfield megaprojects and brownfield projects. Saad obtained a B.S. in Mechanical Engineering from California State University, Long Beach (CSULB) in 2011 and a Master of Engineering in Construction Engineering and Management from King Fahd University of Petroleum and Minerals (KFUPM) in 2024. He is a certified Project Management Professional (PMP) with demonstrated expertise in delivering complex multidisciplinary projects in high-impact industrial environments. He can be contacted at saad.wahaib@aramco.com



Abdul Rahman Habib

Kingdom of Saudi Arabia



Abdul Rahman Habib, ME, CEng, MICHemE, PMP, PMI-RMP is Lead Engineer (Process and Project Management) with Saudi Aramco, Kingdom of Saudi Arabia, with over 25 years of international experience in oil and gas, LNG, petroleum refining, petrochemical, and industrial megaprojects. His expertise encompasses project development, process engineering, construction management, energy optimization, risk management, and industrial project execution. He holds MSc and BSc degrees in Chemical Engineering and is a Chartered Chemical Engineer (IChemE). He can be contacted at abdul.rahman.4@aramco.com